

Calibration wind tunnel 3

Technical Facts:

- Contraction Ratio: 5.5:1
- Turbulence Intensity: $>0.2\%$
- Maximum Velocity: 32 m/s
- Pressure Drop: 600 Pa
- Electrical Power: 30 kW
- Deviation from the reference MEASNET speed:
~ 0.2%
- In full accordance with IEC 61400/2013

