

Calibration wind tunnel 4

Technical Facts:

- Contraction Rotation: 4:1
- Turbulence Intensity: >0.2 %
- Maximum Velocity: 30 m/s
- Pressure Drop: 800 Pa
- Electrical Power: 30 kW
- Deviation from the reference MEASNET speed:
~ 0.2%
- In full accordance with IEC 61400/2013

